

ISTALLATION PROCESS:

1.) REMOVE PART #35570 FROM UNDER DRUM HOUSING.

- 2.) TORCH FRONT SECTION OF DRUM HOUSING TO MAKE ROOM FOR CRACKER PLATE
- 3.) WITH CRACKER PLATE IN BACK HOLES LINE UP FRONT HOLES FOR CRACKER PLATE AND DRILL (2) 9/16" HOLES.
- 4.) INSTALL CRACKER PLATE USING EXISTING PLOW BOLTS AND (2) 1/2" BOLTS PROVIDED
- 5.) ADJUST CRACKER PLATE USING PLOW BOLT AND SLOTTED HOLE IN REAR (ADJUSTMENT SHOULD BE APPROX. 1/16" TO 1/8" AWAY FROM CRACKER KNIVES)

THIS DRAWING IS THE PROPERTY OF KOOIMA CO. AND IS PROVIDED WITH THE UNDERSTANDING THAT IT NOT BE USED IN ANY WAY DETRIMENTAL TO THE INTERESTS OF KOOIMA CO. DRAWN BSM DATE 8-24-99		Kaima Canpan,
CHECKED	DATE	2638 310th Street Phone (712) 476-5600
SCALE 1:5	BREAK ALL EDGES .03 X 45°	Rock Valley, Iowa 51247 FAX (712) 476-5403
DIMENSIONS ARE IN INCHES TOLERANCES UNLESS SPECIFIED FRACTIONAL ± 1/32 3 PLACE ± .005 2 PLACE ± .020 ANGULAR ± 1°		INSTALLATION PRINT
		PART NO. 5400
MATERIAL AS NOTED		DWG. NO. MISC\40050

OF CRACKER PLATE